



OUTLINE PLANNING PERMISSION

Planning (Northern Ireland) Order 1991

Application No: L/2005/2762/O

Date of Application: 1st November 2005

Site of Proposed Development: Lisnadurk Glebe North, Newtownbutler.

Description of Proposal: 2 storey dwelling and domestic garage.

Applicant: Mr G Loughlin
Address: C/O Agent

Agent: Mr E McCaffrey
Address: McCaffrey Bros
160 Main Street
Lisnaskea
BT94

Drawing Ref: 01.

The Department of the Environment in pursuance of its powers under the above-mentioned Order hereby

GRANTS OUTLINE PLANNING PERMISSION

for the above-mentioned development in accordance with your application subject to compliance with the following conditions which are imposed for the reasons stated:

1. As required by Article 35 of the Planning (Northern Ireland) Order 1991, application for approval of the reserved matters shall be made to the Department within 3 years of the date on which this permission is granted and the development, hereby permitted, shall be begun by whichever is the later of the following dates:-
 - i. the expiration of 5 years from the date of this permission; or
 - ii. the expiration of 2 years from the date of approval of the last of the reserved matters to be approved.


Reason: Time limit.

2. Approval of the details of the siting, design and external appearance of the buildings, the means of access thereto and the landscaping of the site (hereinafter called 'the reserved matters'), shall be obtained from the Department, in writing, before any development is commenced.

Application No. L/2005/2762/O

DC1001MW

Enniskillen Planning Office





- v. Any chimneybreast should be internal, with the chimneystack positioned centrally on the ridge, preferably at the gable end of the dwelling.
- vi. The proposed wall finish, in a colour to be agreed with the Department, should be smooth plaster or roughcast render and painted, or have a dry dash finish. The roofing tiles or slates should be blue/black or dark grey and be flat and non-profiled.

2. Environmental Health comments:-

Any septic tank must be a minimum of 15 metres from the proposed dwelling or any other habitable dwelling.

A consent to discharge sewage effluent must be obtained from DoE, Environment and Heritage Service, as required by The Water (Northern Ireland) Order 1999.

A legal agreement must be obtained in relation to lands used in connection with any septic tank/drainage arrangements where such lands are outside the ownership of the applicant or outside the area marked in red which is the subject of this application.

This agreement must ensure that the lands in question will always be available for the intended purpose and also that any owner/occupier of the proposed development will have access to these lands for maintenance/improvement works as required.

3. Water Service comments:-

Public water supply available, subject to Water Service approval to connect. If required a connection will be granted on approval of a completed Water Service Application Form and payment of the Department's standard charge. Contact Water Service's Customer Services Unit to obtain an application form, or telephone Waterline on 0845 7440088.

4. Foul water sewer not available. The use of a septic tank, (on the basis of one for each dwelling) is subject to the necessary written consent being obtained from the Environment and Heritage Service and the approval of the local District Council Environmental Health section.

Where approval to the use of a septic tank disposal system is granted and the applicant wishes the Water service to provide a periodic desludging service the applicant must complete the necessary 'Form of Agreement' and adhere to the construction requirements contained therein. Contact Water Service's Customer Services Unit to obtain a 'Form of Agreement' form, or telephone Waterline on 0845 7440088.


5. Surface water sewer not available. Surface water must not be taken to the foul sewer. Where it is proposed to discharge surface water to a river, stream or watercourse prior written consent for such discharge must be obtained from the Department of Agriculture's River Agency.

6. To ensure compliance with the Water and Sewerage Services (Northern Ireland) Order 1973, as amended 1993, consultation with Water Service is essential at design stage with regard to the following matters:

Application No. L/2005/2762/O

DC1001MW

Enniskillen Planning Office





Reason: To enable the Department to consider in detail the proposed development of the site.

3. A landscaping scheme shall be submitted simultaneously with the detailed drawings (for the development hereby approved) at the Reserved Matters stage. Any trees or shrubs which may be damaged or die within a period of 5 years from the date of planting shall be replaced by plants of similar species and size at the time of their removal. All landscaping shall take place within the first available planting season after the commencement of the development. The plans and particulars submitted shall include details of the existing tree/hedges to be retained, site preparation, planting methods, medium and additives together with the species, size and time of planting, presentation, location, spacing and numbers of all trees and shrubs to be planted and the proposed time of planting.

Reason: To ensure the provision, establishment and maintenance of a high standard of landscaping in the interests of visual amenity.

4. The existing mature trees and vegetation along the entire site boundaries shall be retained except where it is required to provide sight lines. No trees or vegetation shall be lopped, topped or removed without the prior consent in writing of the Department, unless necessary to prevent danger to the public in which case a full explanation shall be given to the Department in writing at the earliest possible moment.

Reason: In the interests of visual amenity.

5. A scale plan at 1:500 shall be submitted as part of the reserved matters application showing the access to be constructed in accordance with the attached form RS1.

Reason: To ensure there is a satisfactory means of access in the interests of road safety and the convenience of road users.


Informatives

1. You are advised that in order to meet the requirements of the Department's Design Guide for Rural Northern Ireland, the form, shape and materials will normally fall within the following parameters:-
 - i. The width of the dwelling frontage, in the case of 2 storey dwellings, should not exceed 14 metres and up to a maximum of 18 metres for single storey dwellings or 20 metres if the roofline is broken or frontage set back.
 - ii. The external gable depth (front to back) of 2 storey dwellings should not exceed 9 metres and only 7 metres in sensitive locations.
 - iii. The roof pitch should be within the range 35 to 40 degrees except when gable depth is below 7.5 metres, then 45 degrees is acceptable.
 - iv. The front elevation should not have any projection or return other than a simple pitched roof storm porch if desired. 2 storey: the porch projected to first floor, if central may be acceptable.

Application No. L/2005/2762/O

DC1001MW

Enniskillen Planning Office





(a) septic tank emptying;


Contact Water Service's Customer Services Unit or telephone Waterline on 0845 7440088.

8. The applicant is advised to contact Water Service through its Customer Service's Unit or Waterline on 0845 7440088 upon receipt of this decision to discuss any issues of concern.
9. If during the course of developing the site the developer uncovers a pipe not previously evident the local Water Service should be notified immediately in order that arrangements may be made for investigation and direction in respect of any necessary measures required to deal with the pipe.
10. This permission does not alter or extinguish or otherwise effect any existing or valid right of way crossing, impinging or otherwise pertaining to these lands.
11. This permission does not confer title. It is the responsibility of the developer to ensure that he controls all the lands necessary to carry out the proposed development.
12. This permission authorises only private domestic use of the proposed garage and does not confer approval on the carrying out of trade or business there from.

12. Northern Ireland Electricity comments:

'The applicant's attention is drawn to the attached information from Northern Ireland Electricity'.

Dated: 31st July 2006





Authorised Officer

Application No. L/2005/2762/O

DC1001MW

Enniskillen Planning Office








PROPOSED SITE

LISNADURK, NEWTOWNBUTLER

Scale 1:2500

Drawing  Number... 01... 

crown copyright reserved



GEONCALICA

GEONCALICA

GEONCALICA

LONCALICA

246250 246500 246750 247000 247250 247500



Scale: 1:8000